

GOVERNMENT OF TRIPURA  
**DIRECTORATE OF INFORMATION TECHNOLOGY**

ITI Road, Indranagar, Agartala – 799 006

No.F.5(69)/DIT/Acctt/2024/ 704


17<sup>th</sup> February, 2025

Short Notice Inviting Quotation

Sealed quotations are hereby invited by the Directorate of Information Technology, Government of Tripura, ITI Road, Indranagar, Agartala-6 for renovation work of false ceiling tiles and new floor carpet of the VIP lounge of Smart Training Centre at ground floor of IT Bhavan. Bill of Quantities enclosed as Annexure-I.

Terms and Conditions

1. Interested agencies/quotationer submit their rate quotations specifying taxes etc.
2. Interested agencies/quotationer collection of the work description from the Directorate of Information Technology, Govt. of Tripura, Indranagar, Agartala.
3. Interest bidder should submit the Short Notice Inviting Quotation reference no & date with their respective reference no. & date.
4. Last date of submission of rate quotation is on or before 28/02/2025 upto 2 PM along with the following documents.
5. GSTN registration No.
6. Photo copy of PAN card.
7. Copy of Trade License.
8. DIT reserves the right to accept or reject, in full or in part, any or all the offers without assigning any reason whatsoever. DIT does not bind itself to accept the lowest on any bid and reserves the right to reject all or any bid or cancel the SNIQ without the vendor having the right to object to such re-issue.

  
(Jeya Ragul Geshan B, IFS)  
Director, IT  
Govt. of Tripura

## ANNEXURE - I

## Bill of Quantities

**Name of Work :- Renovation Work- False Ceiling, Carpet of VIP Waiting hall at Ground floor of IT BHAVAN Indranagar Agartala Tripura (West).**

| Sl. code                            | DESCRIPTION  | Nos | L     | B   | H/D | QTY   | unit | RATE | AMOUNT |
|-------------------------------------|--|-----|-------|-----|-----|-------|------|------|--------|
| 1                                   | 11.37.1<br>Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595 mm of approved texture, design and patterns having NRC (Noise Reduction coefficient) of 0.50 (minimum) as per IS8225:1987, light reflectance of 85% (minimum). Noncombustible as per BS:476 (part-4), fire performance as per BS:476 (part 6 & 7), humidity resistance of 100%, thermal conductivity < 0.043 W/m K as per ASTM 518:1991, in true horizontal level suspended on interlocking metal T-Grid of hot dipped galvanized iron section of 0.33mm thick (galvanized @ 120 grams per sqm including both sides) comprising of main T runners of size 24x38 mm of length 3000 mm, cross - T of size 24x32 mm of length 1200 mm and secondary intermediate cross-T of size 24x32 mm of length 600mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanized mild steel items (galvanizing @ 80 grams per sqm) i.e. 50 mm long, 8 mm outer diameter M-6 dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 85x25x25x2 mm. Galvanized iron perimeter wall angle of size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm center to center and 40mm long dry wall S.S screws. The work shall be carried out as per specifications, drawing and as per directions of the Engineer-in-Charge. With 15 mm thick regular edged light weight calcium silicate false ceiling tiles. | 1   | 9.52  | 3.6 |     | 34.27 |      |      |        |
|                                     | Toilet   | 1   | 3.5   | 3.9 |     | 13.65 |      |      |        |
|                                     | Waiting room   | 1   | 47.92 |     |     | 47.92 | sqm  |      |        |
| 2                                   | MR<br>Providing & fixing in position of floor pvc carpet and top covered with premium wool carpet flooring complete work.  | 1   | 3.8   | 3.6 |     | 13.68 | sqm  |      |        |
| Total Amount (including all tax)Rs. |  |     |       |     |     |       |      |      |        |